7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detailed abstract estimate of restoring Cheluvanahalli Tank Regd. No. 162 of Kolar Taluk.

Items of work	Per	Rate	Quality
		Rs. a. p.	
Bund—			
Earthwork embankment with well consolidation, watering and tamping.	C.yds.	0 3 0	8,884
Clearing silt from the breach	,,	0 2 0	742
Ordinary earth banking to breach, with well consolidation ..	,,	0 3 0	2,400
Puddlework with consolidation	,,	0 6 0	380
Earthwork banking selected earth for the front portion of the breach with watering and tamping.	,,	0 4 0	1,958
Baling water	Lumpsum	Rupees	..
Jungle clearing	,,	,,	..
Turfing	C.yds.	0 0 9	5,180
Grade stones including cutting figures and painting, fixing, etc., complete.	Each	1 8 0	16
Do do Index stones	,,	0 8 0	16
B. M. stones	,,	2 0 0	2
Register and date stone	,,	3 0 0	1
Guage stone	,,	10 0 0	1
Rough stone work old, removing and re-building with new jelly	C.yds.	0 8 0	476
Do new	,,	1 0 0	2,063
Total for bund ..	....	....	..
Sluice—			
Earthwork, cut opening the bund and refilling	C.yds.	0 3 6	40
Earthwork excavating foundation	,,	0 2 0	13
Concrete in surki mortar	C.ft.	0 3 0	235
Burnt brick in surki mortar	,,	0 4 6	238
Burnt stone slabs	S ft.	0 5 0	169
Plastering with surki mortar	S.qr.	3 0 0	1·66
Plug with rod, etc.	Lumpsum	Rupees	..
Total for sluice No. 1 ..	....	....	..
Total for 2 sluices ..	....	....	..
Waste weir—			
Earthwork	C.yds.	0 3 0	65
Burnt brick in surki mortar	C.ft.	0 4 6	532
Burnt stone slabs 6" thick	S ft.	0 5 0	285
Plastering with surki mortar	Sqr.	3 0 0	7·46
Rough stone work new	C.yds.	1 0 0	65
Do old	,,	0 8 0	20
Providing juggles for the coping slabs	Each	1 0 0	12
Total for weir ..	....	....	..
Total of all the sub-heads ..	....	....	..
Contingencies at 5% ..	....	....	..
Grand Total ..	....	....	..

N. ANANDALWAR,
Executive Engineer.

THE BANK OF MYSORE, LIMITED, BANGALORE.

Statement of the affairs of the Bank of Mysore, Limited, for the week ending 17th April 1924, published under Article 141 of the Articles of Association.

LIABILITIES	Rs.	ASSETS	Rs.
To Capital Receipts ...	20,00,000	By cash in hand and at Bankers	21,95,892
,, Reserve Funds ...	13,25,000	,, loans and cash credit accounts	1,15,44,380
,, Public and other deposits ...	1,40,79,000	,, bills discounted ...	3,98,457
,, Sundries ...	4,16,928	,, investments	29,31,562
		,, balance at Agencies ...	26,080
(Annas and pies omitted).		,, dead stock	6,11,148
		,, sundries	1,13,409
Total ...	1,78,20,928	Total ...	1,78,20,928

R. W. O'BRIEN,
Secretary.